CLOSEOUT, TURNOVER & LESSONS-LEARNED PLAN

Corporate Operations Center | Final-Phase Management Playbook

Corporate Construction Project Management Portfolio Simulation

1. Closeout Strategy

Closeout begins before substantial completion. The objective is to deliver a fully functional facility, complete contract records, trained operations staff, resolved deficiencies, complete financial reconciliation, and a defensible record of project performance. Closeout progress is tracked by responsible party, forecast date, status, percent complete, and retention/final-payment linkage.

Closeout Workstreams

Workstream	Required Deliverables	Acceptance Evidence
Permits / CO	Final inspections, corrections, Certificate of Occupancy	AHJ sign-off
Commissioning	Startup, TAB, controls checkout, FPT	CxA final report
O&M Manuals	Approved electronic manuals, data sheets, maintenance requirements	Owner receipt / approval
Training	Mechanical, electrical, controls, security/IT training	Attendance + recorded sessions
As-Builts	Field redlines and record drawings	A/E and owner turnover
Warranties	Certificates, contacts, start dates	Warranty matrix
Punch List	Room-by-room deficiency closure	Architect/owner verification
Financial	Final changes, retainage, claims, final payment	Final cost reconciliation
Archive	Contracts, RFIs, submittals, tests, reports, photos	Indexed project archive

2. 90/60/30-Day Turnover Rhythm

Timing	PM Actions
90 days before turnover	Audit closeout requirements by trade; issue deficiency report; confirm commissioning schedule; validate O&M/as-built templates.
60 days	Begin draft O&M review, training schedule, attic stock inventory, warranty matrix and punch-prevention walks.
30 days	Lock owner training dates; confirm final inspection path; run pre-punch by zone; reconcile open changes and outstanding submittals.
Substantial completion	Issue punch list; secure temporary/final occupancy approvals; complete owner training; transfer key systems and access.
Final completion	Verify all punch, closeout documents, warranties, final lien releases, cost reconciliation, archive and lessons learned.

3. Punch List Management

- Pre-punch by trade before architect/owner punch to reduce final deficiencies.
- Assign each item to a specific trade and due date; photos and room/area tags are required.
- Do not mark complete until reinspection verifies closure.
- Track life-safety, accessibility, envelope and operational deficiencies separately as turnover-critical.
- Escalate aging punch items through retention and final-payment controls.

4. Financial Closeout

- Resolve pending change proposals and backcharges before final completion.
- Reconcile contract values, approved changes, stored materials, retainage, allowances and owner-direct costs.
- Verify unconditional/final lien releases as required by contract and law.
- Confirm all subcontractor closeout obligations before release of final retention.
- Archive final cost report and variance narrative by cost code.

5. Commissioning & Training

- Maintain integrated commissioning schedule covering equipment startup, controls point-to-point, TAB, deficiency correction and functional performance testing.
- Coordinate owner facilities staff availability early; training is not a last-day activity.
- Use approved O&M information during training so field demonstrations align with final documentation.
- Record critical systems training and provide indexed files to the owner.

6. Lessons-Learned Framework

Topic	What Worked	What To Improve	Future Standard
Preconstruction	Early long-lead identification and bid packaging	Design/MEP coordination needed earlier maturity	Run constructability/BIM risk review before 100% CDs
Schedule	Localized recovery avoided major milestone drift	Envelope recovery started after float was already consumed	Trigger recovery at defined float thresholds
Procurement	RTUs and gear were released early	Storefront review required multiple cycles	Back-plan facade submittals with more review contingency
Cost	Forecast structure made exposure visible	Elective scope competed with contingency	Separate owner enhancement reserve from contingency
RFI / Design	Most RFIs closed quickly	Utility and Grid C7 clashes affected field work	Use targeted existing-condition verification and zone sign-off
Safety	Observation/near-miss culture produced corrections	Leading-edge/scaffold exposure recurred	Increase focused audits during high-risk overlap phases
Quality	Hold-point inspections caught issues before concealment	MEP coordination deficiency reached installation area	Require model/field coordination sign-off before rough-in

7. Final KPI Scorecard Template

KPI	Final Result	Target	Variance	Narrative
Safety recordables	TBD	0	TBD	
Final completion	TBD	03/19/2027	TBD	
Final cost	TBD	<= authorized budget	TBD	
Change order rate	TBD	Track gross approved / baseline	TBD	
RFI average turnaround	TBD	<5 business days	TBD	
Punch aging	TBD	No turnover-critical open items	TBD	
Closeout completeness	TBD	100%	TBD	

8. Portfolio Use Note

This project is a fictional but internally consistent portfolio simulation designed to demonstrate corporate construction project-management methods. In an interview, describe it as a hands-on project controls simulation and explain the assumptions, calculations, management decisions, and control logic. Do not present it as paid field experience on a real owner project.