PROJECT MANAGEMENT PLAN

75,000 SF Corporate Operations Center | North Carolina | $20.6M Baseline Budget

Corporate Construction Project Management Portfolio Simulation

Project Attribute	Baseline
Delivery Model	General Contractor / subcontracted trade packages
Facility	75,000 SF ground-up corporate operations center
Baseline Budget	$20,600,000
Current Revised Budget	$21,057,000
Contract Start	January 12, 2026
Contract Finish	March 19, 2027
Status Date	September 11, 2026
Current Phase	Structure / envelope / MEP rough-in
Overall Planned Progress	51.7%
Overall Actual Progress	49.9%
Recordable Incidents	0

1. Executive Project Charter

Purpose: deliver a safe, code-compliant, durable corporate operations center that consolidates regional operations, training, IT/security, executive support, and facilities functions. The project is managed to a controlled baseline with disciplined change governance, transparent forecasting, and documented quality and safety controls.

Business Objectives

- **Operational readiness:** achieve Certificate of Occupancy and owner turnover by March 19, 2027.
- **Financial control:** maintain forecast within the authorized project funding envelope and protect contingency for true unknowns.
- **Schedule reliability:** manage critical long-lead equipment, weather-tight milestones, MEP coordination, commissioning, and closeout with documented recovery actions.
- **Safety:** zero recordable incidents and immediate closure of high-severity observations.
- **Quality:** pass first-time inspections where practical; verify envelope, structural, MEP, and finish systems against approved documents and manufacturer requirements.
- **Stakeholder confidence:** maintain no-surprise reporting through weekly OAC meetings, decision logs, and monthly executive reporting.

Scope Summary

- Site clearing, earthwork, storm/sanitary/water utilities, paving, sidewalks, landscaping and site furnishings.
- Cast-in-place foundations and slabs; structural steel frame, deck and elevated slab.
- Roofing, air/water barrier, exterior framing, curtain wall/storefront, exterior doors and hardware.
- HVAC, controls, plumbing, fire protection, electrical distribution, generator interfaces, lighting, low voltage and security.
- Interior framing, drywall, ceilings, flooring, paint, millwork, doors/hardware and owner IT/AV integrations.
- Testing, commissioning, TAB, punch list, O&M manuals, training, as-builts, warranties, Certificate of Occupancy and final handover.

Out of Scope / Owner-Direct Assumptions

- Furniture procurement beyond installation coordination.
- Business move-management and employee relocation.
- Enterprise software configuration beyond construction-side infrastructure coordination.

- Post-occupancy operations after warranty turnover, except documented warranty response obligations.

2. Governance & Organization

Role	Primary Accountability	Escalation / Decision Rights
Executive Sponsor	Funding, major scope decisions, strategic outcomes	Approves material budget/scope changes
Owner Project Manager	Owner requirements, decisions, finance interface	Daily owner-side authority
Construction Project Manager	Scope, schedule, cost, risk, changes, procurement, reporting	Controls baseline and escalates forecast/decision risk
Superintendent	Field execution, sequencing, logistics, daily coordination	Stops work for safety/quality constraints
Project Engineer	RFIs, submittals, document control, inspections, closeout	Routes technical issues and maintains logs
Safety Manager	Site safety plan, audits, incident response	Stop-work authority
QA/QC Lead	Inspection/test plans, deficiency closure	Rejects nonconforming work
Architect / Engineers	Design intent, submittal/RFI review, code compliance	Technical design authority
Trade Partners	Means/methods, manpower, procurement, installation	Trade execution and recovery plans

RACI Snapshot

Control	PM	Super	PE	Owner	A/E	Trade
Baseline schedule	A	R	C	C	C	C
Cost forecast	A/R	C	C	C	I	I
RFI management	A	C	R	I	R	C
Submittals	A	C	R	I	R	R
Change control	A/R	C	C	A/C	C	C
Safety	A	R	C	I	I	R
Quality	A	R	R	I	C	R
Closeout	A	R	R	C	C	R

3. Schedule Management Plan

The baseline schedule is managed as a WBS-driven critical-path plan. The project manager reviews milestone health, critical/near-critical activities, 3-week look-ahead constraints, trade manpower, submittal/procurement dates, and actual-vs-planned progress each week.

Current Schedule Position

Metric	Current	Management Interpretation
Planned progress	51.7%	Baseline expectation at status date
Actual progress	49.9%	1.8 percentage points behind plan
Primary near-term constraint	Weather-tight milestone	South elevation framing and glazing sequencing
MEP constraint	Area A overhead rough-in	Grid C7 coordination issue must close before enclosure
Critical procurement	Main electrical gear	Factory ship date confirmed; expedite gate maintained
Recovery approach	Localized acceleration / resequencing	Add access equipment, protect dry-in, coordinate by zone

Schedule Control Procedure

- Update actual starts/finishes and percent complete weekly from superintendent/trade verification.
- Review critical and near-critical path before the OAC meeting; identify slippage, float erosion, and milestone exposure.
- Issue a 3-week look-ahead that includes activities, constraints, manpower, inspections, submittals, equipment deliveries, and owner decisions.
- Require written recovery plans for activities that materially threaten critical milestones.
- Tie procurement dates to required-on-site dates and submittal approvals; do not treat procurement as a separate administrative log.
- Document owner/design decisions with required-by dates so decision latency becomes visible as schedule risk.

4. Cost & Forecasting Plan

Cost control uses original budget, approved budget transfers/changes, revised budget, committed cost, actual cost, estimate-to-complete (ETC), forecast-at-completion (FAC), and variance. The workbook distinguishes gross approved changes from internal contingency/VE transfers so management can see both scope movement and net budget impact.

Cost KPI	Amount
Original baseline budget	$20,600,000
Current revised budget	$21,057,000
Forecast at completion	$20,550,000
Forecast variance / remaining headroom	$507,000
Actual cost to date	$10,215,000
Gross approved changes	$564,500

Monthly Cost Review Standard

- Validate commitments against executed subcontracts, purchase orders, allowances, and owner-direct packages.
- Reconcile actuals to pay applications and verify stored material, retainage, pending backcharges, and unapproved exposure.
- Reforecast ETC by cost code using remaining quantities, trade projections, known changes, and risk allowances.
- Review all potential changes separately from approved budget movement to avoid hiding exposure.
- Protect contingency: elective owner enhancements should receive explicit funding approval rather than silently consuming contingency.
- Escalate any forecast trend that reduces headroom below the project-defined threshold.

5. Change Management

Every scope/cost/schedule change follows a controlled lifecycle: identify -> document -> estimate -> validate entitlement -> assess schedule impact -> owner decision -> budget authorization -> execute -> update forecast and contract records.

Change Control Gate	Required Evidence
Identification	RFI, owner request, field condition, design bulletin, code/AHJ direction
Pricing	Labor/material/equipment detail, subcontractor quotes, markups, credits, allowances
Schedule analysis	Affected activity, days, float, resequencing or acceleration options
PM validation	Scope entitlement, duplication check, cost reasonableness, budget code
Owner approval	Written authorization before execution except emergency work
Incorporation	Update change log, contract value, cost forecast, schedule and meeting minutes

6. Procurement & Submittal Strategy

Long-lead procurement is treated as a schedule workstream. The critical watch list includes structural steel, curtain wall/storefront, packaged rooftop units, main electrical gear, and technology equipment. Each package tracks bid, award, submittal, required-on-site, forecast delivery, and recovery actions.

- Early-release long-lead equipment after design confidence and owner authorization.
- Submittal due dates are back-planned from fabrication lead time, shipping, receiving, inspection, and required-on-site milestones.
- Weekly vendor confirmation is required for critical factory ship dates; verbal assurances are not sufficient.
- When lead time threatens the schedule, evaluate approved alternates, split shipments, resequencing, local staging, and expedite cost against schedule value.

7. RFI, Submittal & Document Control

Control	Target / Rule

RFI turnaround	Target <5 business days; escalate overdue critical RFIs immediately
RFI content	One issue per RFI; field photos/sketches; requested response date; cost/schedule impact flag
Submittal review	Back-plan review due date from required-on-site; track revisions independently
Revision control	Field uses current approved documents only
Decision log	Owner decisions include due date, options, recommended path and impact of delay
Meeting minutes	Issue within 24 hours; actions assigned with owner and due date

8. Risk Management

Risks are scored Probability x Impact on a 1-5 scale and categorized Low, Medium, High, or Critical. Each high-value risk has a trigger, response, owner, target date, and residual score. Risks that have occurred are moved to the Issues Log so they are actively resolved rather than passively monitored.

Top Risk	Score	Response
Electrical gear delivery slip	15 / High	Weekly factory calls, expedite gate, temporary power contingency
Weather-tight milestone slip	15 / High	Daily envelope huddles, split shipments, temporary dry-in
Contingency erosion from changes	16 / High	Change governance, owner funding, finish freeze
MEP coordination rework	12 / High	BIM clash closure by zone before rough-in
Late owner finish decisions	12 / High	Decision dashboard and OAC escalation

9. Safety Management

The project safety approach combines pre-task planning, daily huddles, weekly audits, leading-edge/fall-protection controls, excavation controls, equipment/pedestrian separation, scaffold verification, housekeeping, incident/near-miss reporting, and documented corrective action. The project currently has zero recordable incidents.

- Stop-work authority applies to all project personnel.
- High/critical observations require immediate containment and documented closure before exposure resumes.
- Near misses are investigated for system causes, not only worker behavior.
- Trade trend data is reviewed weekly to target toolbox talks and field audits.

10. Quality Management

Quality is built around preparatory meetings, first-work inspections, hold points, third-party/special inspections, manufacturer requirements, mockups, test reports, deficiency logs, and documented reinspection. Key envelope and MEP installations are verified before concealment.

Quality Hold Point	Verification
Foundation reinforcing	Pre-pour inspection / special inspector sign-off
Concrete	Mix design, cylinders, placement records, FF/FL testing
Structural steel	Bolt tension / weld inspection / survey
Air barrier / envelope	Substrate inspection, mockup, transition inspection, water testing
Roofing	Manufacturer requirements and seam testing
MEP rough-in	Approved coordination, inspection before close-in
Commissioning	Startup, TAB, controls checkout, functional performance testing

11. Communications & Meeting Cadence

Meeting / Report	Cadence	Core Agenda
Daily field huddle	Daily	Safety, manpower, work areas, deliveries, constraints
Trade coordination	Weekly	3-week look-ahead, BIM/clashes, inspections, procurement
OAC meeting	Weekly	Schedule, cost, RFIs/submittals, changes, decisions, risks

Safety meeting	Weekly	Leading indicators, observations, near misses, corrective actions
Executive status report	Monthly	Health summary, milestones, forecast, major risks, decisions
Closeout review	Monthly beginning 90 days before turnover	O&M, as-builts, warranties, training, punch, CO

12. Closeout & Turnover Plan

- Begin closeout tracking months before substantial completion; do not wait for punch list.
- Tie O&M manuals, warranties, as-builts, attic stock, training and test reports to trade retainage/final payment requirements.
- Run punch by room/zone with assigned owner and due date; verify closure before removing item.
- Coordinate TAB, controls, commissioning, owner training and seasonal testing.
- Reconcile all open changes and final cost exposure before final completion.
- Conduct a structured lessons-learned retrospective and archive project records.

13. Project Success Criteria

KPI	Target
Safety	0 recordable incidents
Schedule	CO and turnover by 03/19/2027
Cost	FAC at or below authorized revised budget
Quality	No major unresolved deficiencies at turnover
RFI performance	Critical RFIs turned within required dates
Closeout	100% turnover documents, training and warranties complete
Stakeholder	Owner decisions and executive reporting maintained without material surprise